ATLANTIC AVENUE BUILDERS LLC

General Contractor | 455 Atlantic Ave, Brooklyn NY 11217 | procurement@aabuilders.example

REQUEST FOR QUOTATION - MATERIALS ONLY

RFQ No.	AAB-0417	**Issued**	10/09/2026
Project	210 Bergen St Residential - Amenity Level	**Quotes due**	10/16/2026 5:00 PM
Deliver to	210 Bergen St, Brooklyn NY (site, no forklift)	**Buyer**	J. Castellano

Line	Description	Qty	U/M	Spec Section	Unit Price	Ext.
1	SS 304 SHT 1.5MM 1220X2440 BA	6	SH	05 75 00 Decorative Formed Metal		
2	ALUM 5005-H34 CLR ANOD .063 4X8 (AAMA 611 CL I)	20	SH	05 75 00 Decorative Formed Metal		
3	6063-T52 RECT TUBE 2 X 4 X .125 MILL 24'-0"	12	EA	05 50 00 Metal Fabrications		
4	6061-T651 PLT .500 X 48 X 144	2	EA	05 50 00 Metal Fabrications		
5	SS FLAT BAR 1/4 X 2 TYPE 316 12'	15	EA	05 73 00 Decorative Metal Railings		
6	BRASS SHT C260 1/2 HD .040 36X96	8	SH	05 75 00 Decorative Formed Metal		
7	GALV SHT 20GA	40	SH	07 62 00 Sheet Metal Flashing and Trim		
8	ALUM SHT .040 5052 MILL 4X8	30	SH	07 62 00 Sheet Metal Flashing and Trim		

GENERAL REQUIREMENTS

1. Provide mill test reports (MTRs) for ALL metal items with delivery.
2. State country of origin for each line on the quotation.
3. Project is pursuing LEED v4.1. Provide recycled content (pre-/post-consumer %) documentation per line.
4. Anodized finishes to comply with AAMA 611, Class I clear.
5. Quote firm for 30 days. Freight to be shown separately.
6. Substitutions require written approval from Architect. Do not substitute alloys or grades.
7. Dimensions per architectural drawings A-501 through A-508 (metric details on A-504).

Supplier: _____ Signature: _____ Date: _____